



ADDENDUM

DATE: May 5, 2017

ADD. NO.: 1

PROJECT: DEMOLITION OF EXISTING STRUCTURES PROJECT

BID. NO.: 2017-06

FROM: Tim Ogden, City Manager

TO: All Bidders

PAGES: 1

This Addendum forms a part of the Contract Documents and modifies the original Proposal, Technical Specifications and Agreement, dated April 2017. Acknowledge receipt of this Addendum when submitting the Proposal. Failure to do so may subject the bidder to disqualification.

- 1-1 Existing building contains a concrete vault approximately 10'L x 8'W x 8'H. The walls are approximately 10" thick. The vault shall be completely removed with the building.
- 1-2 Bid shall include cost for complete removal of structures (including footings), concrete flatwork, and asphalt on the site. Site shall be graded smooth to drain, and covered with 3" of $\frac{3}{4}$ " crushed rock.

End of Addendum